

Emission Test Certificate

Wednesday April 28th, 2021

Supplier: Compass Materials Pty Ltd (Unit 16, 100 New Street, Ringwood, VIC, 3134, Australia)

Sample Description: Prime Oak Engineered Flooring, Dimension 1900mm*190mm*15/4.

Date Tested: April 2021 (Tested through FORAY Laboratories - NATA Accreditation 1231)

Test Method: ASTM D5116:2017 "Standard Guide for Small-Scale Environmental Chamber

Determinations of Organic Emissions from Indoor Materials/Products".

Emission Data (24 hrs exposure):

Green Building Council of Australia Green Star Design & As Built V1.3 13.1.2B & 13.2 Green Star Interiors V1.3 - 12.1.2B	Prime Oak Engineered Hardwood Flooring
Total Volatile Organic Compound Emission Rate limit:	Total Volatile Organic Compound Emission
≤0.500 mg/m²/hr	Rate: 0.010 mg/m²/hr
Formaldehyde Emission Rate limit:	Formaldehyde Emission Rate:
≤0.100 mg/m²/hr	0.012 mg/m²/hr

We hereby certify that Prime Oak Engineered hardwood flooring is meet with formaldehyde emission requirements of Green Star Design & As Built – Green Star Interiors, Green Building Council of Australia.

Dr. Vyt Garnys

PhD, BSc(Hons) AIMM, ARACI, ISIAQ

ACA, AIRAH, FMA

Managing Director and Principal Consultant

Ch.S. Si Conth

Dr. Srikanth C. Srivatsa PhD (Chemistry) Scientific Consultant Dr. Tuan Duong
PhD, B Eng. (Chemical)
Senior Consultant

V2103086A